



## Town of Medley

Office of Capital Projects & Development Services  
7777 NW 72 Avenue, Medley, Florida 33166

Date:	<b>December 14, 2016</b>
Subject:	<b>NW 79 Avenue from NW 77 Street to NW 79 Place Paving and Drainage Imp.</b>
Solicitation Number:	<b>ITB 2017-002</b>
OCPDS Number:	SW-0115
Opening Date / Time:	<b>January 5, 2017</b>
ADDENDUM Number:	<b>2</b>

### ***To all interested proposers:***

The Town of Medley defines a solicitation "Addendum" as an addition to or amendment of the original terms, conditions, specifications, or instructions of a procurement solicitation (e.g. Invitation for Bids, Request for Proposals or Request for Qualifications), including but not limited to questions and answers, which are considered a material part of the solicitation.

### **Please note the following updates:**

Addendum #2 does the following:

**Revisions to the Solicitation Documents as follows (additions underlined, ~~deletions strikethrough~~):**

Attached Part 2-8A and Part 2-9

RFI No.	Question	Responses
2-01	<i>The Utility adjustment of manholes and valves.</i>	<i>Please use pay items 425-5-1 and 425-6 (See Plan Set Sheet 2, Summary of Quantities, and page 2-8A of the project manual)</i>
2-02	<i>The asphalt curb pad thickness</i>	<i>Please use 2" of any type of asphalt. Price of asphalt curb pad to be included under 520-1-10</i>
2-03	<i>Missing most of the drainage structures</i>	<i>Please refer to Plan Set Sheet 2, Summary of Quantities, and page 2-8A of the project manual</i>
2-04	<i>Missing a Maintenance of traffic pay item to address flaggers and MOT shifts</i>	<i>Flaggers and shifts to be paid under pay item 102-1 (See Plan Set Sheet 2, Summary of Quantities, and page 2-7 of the project manual)</i>
2-05	<i>Missing a removal of contaminated subsoil material</i>	<i>There is no evidence of contaminated soils within the project limits. Please refer to letter from Pollution Remediation Section Unit provided by Miami-Dade County Regulatory and Economic Resources Department.</i>
2-06	<i>Bid form included in original solicitation is missing items 21 to 30 (most of them for drainage structures as per summary of pay items plans). Please clarify.</i>	<i>Addendum is being processed to add this page to the project manual.</i>
2-07	<i>Is this project funded by FDOT?</i>	<i>No, however, please note that project is to be constructed as per FDOT specifications.</i>
2-08	<i>Will special wages or Davis Bacon apply?</i>	<i>No.</i>
2-09	<i>Will buy American act apply?</i>	<i>No.</i>





## Town of Medley

Office of Capital Projects & Development Services  
7777 NW 72 Avenue, Medley, Florida 33166

2-10	<i>As plans are in FDOT format and Bid items are in FDOT format, will FDOT specs apply for construction and billing?</i>		<b>Yes, project to be constructed per FDOT specs.</b>
2-11	<i>As per plan sheet No. 7 Optional Material Tabulation. Will RCP be the only material allowed in this project?</i>		<b>Yes, RCP is the only allowed material.</b>
2-12	<i>There is no item for trench restoration. It is to be included into pipe installation items?</i>		<b>Per FDOT Spec 430: The cost of restoring the site, as specified in 125-11, that is disturbed, solely for the purpose of constructing pipe culvert, will be included in the Contract unit price for the pipe culvert.</b>
2-13	<i>As per note 40 in plan sheet No. 9 the removal of existing Storm Sewer must be included in Clearing and Grubbing. In revising solicitation and site we found that plans call for removal of 1 EA existing inlet and associated pipe. Do you have information regarding the extension and diameter of said pipe?</i>		<b>Plans call for removal of 3 (three) locations where existing inlets and pipes are to be removed. Information on existing pipe size is unknown since pipes were inaccessible by the time of survey</b>
2-14	<i>There is an existing pipe marked as S(D) in plans. Is this pipe and existing Storm Sewer line and also need to be removed?</i>		<b>No, the pipe marked as S(D) Storm sewer is not to be removed.</b>
2-15	<i>As per note 4 in plan sheet No. 9 the contractor must handle contaminated excavated materials. As per FDOT specs (if they are applicable) the contractor must stop work and call FDOT for them to activate their CAR contractor who will handle contaminated soils under a different contract. From past project experience, other agencies assign a dedicated allowance for contaminated material. It is impossible for bidders in this solicitation to quantify contaminated material and know the kind of contamination to properly determine cost for contamination. Please add contaminated soils allowance.</i>		<b>There is no evidence of contaminated materials within the project limits. However, n the even that contaminated materials are found, the normal FDOT process will be followed and a specialty contractor will be engaged in the soil remediation activities.</b>
2-16	<i>Please provide details for conflict structures.</i>		<b>Conflict structures should be designed per index 307 as stated on drainage structures sections. Actual elevation of utilities are provided on the summary of verified utilities and should be verified on the field by contractor prior production of shop drawings for conflict structures.</b>
2-17	<i>Please provide details for aprons, if needed, in ditch bottom inlets to be installed in existing swales and provide item for inlet aprons</i>		<b>No concrete aprons needed for ditch bottom inlets. Collected runoff comes from pervious area only, no high velocities are expected on these swales.</b>
2-18	<i>Is there any enforcement for night work in this project?</i>		<b>Yes, please refer to TCP Note 4 for lane closure restrictions. Contractor can submit an alternative Temporary Traffic Control Plans where temporary pavement is used to maintain two travel lanes at all times</b>



## Town of Medley

Office of Capital Projects & Development Services  
7777 NW 72 Avenue, Medley, Florida 33166

2-19	<p><i>Sheet No. 9, Note 38, states that the existing inlets, manholes and pipe to remain are to be cleaned and desilted and the cost is to be included in pay item no. 430-94-1 (Pipe Desilting up to 24"). The denoted pay item is not included in the bid form or documents, could you please address how this work will be paid?</i></p>		<p><b><i>There are no existing drainage inlets or pipes that are to remain. Therefore, the desilting pay item is not needed.</i></b></p>
------	---	--	--

**BID PROPOSAL  
FOR ITB 2017-002  
NW 79TH AVENUE FROM NW 77TH STREET TO NW 79TH PLACE PAVING AND DRAINAGE IMPROVEMENTS**

No.	Pay Item Number	Description of Work	Unit	Quantity	Unit Price (\$)	Written Unit Price (\$)	Extended Cost (\$)
21	425-1321	Inlets, Curb, Type P-2, <10'	EA	3			
22	425-1322	Inlets, Curb, Type P-2, >10'	EA	1			
23	425-1361	Inlets, Curb, Type P-6, <10'	EA	1			
24	425-1365	Inlets, Curb, Type P-6, Partial	EA	1			
25	425-1451	Inlets, Curb, Type J-5, <10'	EA	1			
26	425-1461	Inlets, Curb, Type J-6, <10'	EA	4			
27	425-1521	Inlets, DT Bot, Type C, <10'	EA	4			
28	425-2-41	Manholes, P-7, <10'	EA	1			
29	425-5-1	Manholes, Adjust Utilities	EA	5			
30	425-6	Valve Boxes, Adjust	EA	3			

Name of Bidder \_\_\_\_\_

Signature of Bidder \_\_\_\_\_



**BID PROPOSAL  
FOR ITB 2017-002  
NW 79TH AVENUE FROM NW 77TH STREET TO NW 79TH PLACE PAVING AND DRAINAGE IMPROVEMENTS**

No.	Pay Item Number	Description of Work	Unit	Quantity	Unit Price (\$)	Written Unit Price (\$)	Extended Cost (\$)
31	430-175-118	Pipe Culvert, Optional Material, Round, 18" S/CD	LF	224			
32	430-175-124	Pipe Culvert, Optional Material, Round, 24" S/CD	LF	144			
33	443-70-4	French Drain, 24"	LF	1279			
34	520-1-10	Concrete Curb and Gutter, Type F	LF	3215			
35	520-3	Valley Gutter, Concrete	LF	190			
36	522-1	Concrete Sidewalk (4" thick)	SY	2114			
37	527-2	Detectable Warnings	SF	162			
38	570-1-2	Performance Turf, Sod	SY	1560			
39	700-1-11	Single Post Sign (F&I, Ground Mount, up to 12SF)	AS	5			
40	700-1-12	Single Post Sign, F&I Ground Mount, 12-20 SF	AS	1			

Name of Bidder \_\_\_\_\_

Signature of Bidder \_\_\_\_\_